Pos	Part no.	Description	Qty	Make/buy	Material / spec	kg each
46	NS6-500	Spread footing (firm ground) with pedestal	1	make	C30/37 XF4 air-entrained, B500C	13200.0
47	NS6-510	Anchor cage 12 × M24 + 4 hinge anchors	1	make	M24 8.8 HDG threaded rod, S355 template ring	143.5
		H TOOLS AND MOULDS				
48	NS6-110-1	Blade mould, lower (pressure side) half on frame	1	make	GRP tooling laminate 12 mm, vinylester tooli	75.4
49	NS6-110-2	Blade mould, upper (suction side) half	1	make	GRP tooling laminate 12 mm	75.4
50	NS6-110-3	Mould frame (RHS 80 × 80 × 4)	1	make	S235 RHS 80×80×4	155.4
51	NS6-115	Root insert fixture (tool)	1	make	S355, machined	9.2
52	NS6-135	Pitch setting gauge (tool)	1	make	Al 6082 + digital inclinometer	1.6
53	NS6-420	Gin pole 3.0 m (erection tool)	1	make	S355 tube 168.3 × 6.3	94.0
		J FASTENERS, CABLES, SITE MATERIALS				
54	NS6-900-01	Stud M12 × 75 10.9 zinc-flake + nut + washer (blade roots)	30	buy	10.9 zinc-flake	0.12
55	NS6-900-02	Bolt M16 × 70 10.9 (hub to drum)	12	buy	10.9 zinc-flake	0.17
56	NS6-900-03	Bolt M20 × 90 10.9 (spindle to bedplate)	12	buy	10.9 zinc-flake	0.32
57	NS6-900-04	HV set M16 × 110 10.9 (yaw inner ring)	16	buy	EN 14399-4	0.26
58	NS6-900-05	Bolt M16 × 70 10.9 (yaw outer ring, pads, caliper)	28	buy	10.9 zinc-flake	0.17
59	NS6-900-06	HV set M20 × 90 10.9 (adapter to tower)	16	buy	EN 14399-4	0.40
60	NS6-900-07	Nut M24 8.8 HDG + plate washer (base, hinge)	44	buy	8.8 HDG	0.15
61	NS6-900-08	Small fasteners kit M8–M12 A4 (cover, spinner, mast, cabinet)	1	buy	A4-70	2.50
62	NS6-800-W1	Cable H07RN-F 4G10 (generator → box)	3	buy	m	0.60
63	NS6-800-W2	Cable H07RN-F 4G10 (box → loop → hand hole)	12	buy	m	0.60
64	NS6-800-W3	Cable NYY-J 4 × 10 (hand hole → cabinet)	4	buy	m	0.50
65	NS6-800-W4	Cable ÖLFLEX 4G1.5 shielded (brake)	16	buy	m	0.10
66	NS6-800-W5	Cable LiYCY 12 × 0.5 (sensors)	16	buy	m	0.12
67	NS6-800-W6	Cable ÖLFLEX 7G1.5 (yaw motors)	16	buy	m	0.15
68	NS6-800-W7	Earthing conductor Cu 50 mm² + ring earth + 2 rods 3 m	1	buy	Cu	18.00
69	NS6-500-M1	Concrete C30/37 XF4 air-entrained (firm ground)	5.5 m³	buy	ready-mix	
70	NS6-500-M2	Rebar B500C (mesh Ø16/150 top + bottom, pedestal cage)	1	buy	≈ 420 kg	420.00
71	NS6-500-M3	Non-shrink grout ≥ 40 MPa, 30 mm under the base flange	60 l	buy		
72	NS6-600-K1	Contactor K1 3-pole NC (mirror contacts) + safety relay PL d	1	buy		2.00
73	NS6-620-PE	Converter, dump chopper, AC module, 48 V module, controller (d	1	make	in-house electronics	45.00

NOTES

1. Masses from the CAD model (cad/turbine_6kw/model6.py) for made parts; supplier data or estimates for bought parts. Full BOM with sources: bom6.csv.

Dimensions mm · ISO 2768-mK · ISO 8015 · first angle projection · edges broken 0.5 unless stated · NOT CHECKED: prototype release only after review

6 kW WIND TURBINE S6 (ICELAND) · FIXED PITCH, STALL CONTROL

BILL OF MATERIALS (2/2)

DRAWING NO.	REV / DATE	SCALE (A3)
NS6-003	B · 2026-11-06	–
MATERIAL	MASS (CALC.)	DRAWN / CHECKED
see lines	see lines	Claude / not checked